

Attachment 1: Clallam County PUD Quote 10572017C

Quote Date: March 24, 2017

Page 1 of 1

Notes to this pricing:

1. FOB: Destination with Freight Pre-Paid and Added (PP&A) to invoice
2. Freight to be recalculated prior to shipment
3. Conductor & accessories to be finalized upon review of plan profile
4. Conductor Lengths for Install: Seven (7) reels @ 3,212' (Tolerance +2% / -2%); Plus Spare: One (1) reel @ 3,212' (+2% / -2%); for a Total of Eight (8) reels.
5. Refundable Reel Deposits for the steel reels: 3M will invoice for the one (1) "Spare" reel upon shipment. However, 3M may defer the invoicing for the seven (7) reels that are used during "installation", for a period of six (6) months from date of shipment; pending the return of empty reels are returned in reusable condition to 3M's strander (Flora, IL); the line item MUST be on the PO.
6. Reels are an International Instrument of Traffic (9803.00.500)
7. Connection hardware to connect dead ends and suspensions to insulator strings are to be provided by the contractor or utility. Drawings of dead ends and suspensions can be provided by 3M
8. On 3-20-2017, CCPUD's Mike Hill confirmed VORTXO Input Form details which generated 3-24-2017 Damper Analysis for quantities & placement
9. Roller Arrays: Subject to tool availability, 3M will loan them to Clallam County PUD for this project, at the customers expense to mobilized/de-mobilize; Arrays must be returned in re-usable condition or they will be charged back.
10. Required Install equipment, i.e. 100-ton press, 10,000 p.s.i. hydraulic pump, & roller arrays, are NOT part of the quote. Customer or their contractor may already have the 100-Ton Press & Pump assembly that is compatible with the 100 dies.

Project Info and Line Description:	
Project Name:	Elwha River Crossing
Original B.O.M. Date:	01-09-2017 (by TNS)
B.O.M Revision (level/date/by):	C / 03-24-2017 / TNS
ACCR Conductor Size:	270-T35
Line Miles/Km (Approximate):	0.76 miles
Number of Circuits:	2
Line Voltage (need EHV parts if >= 345kV):	115kV & 12.47kV
Bundled (ie. Twin, Tri, Quad):	No
Number of Dead End Towers:	2
Number of Take Off Structures:	2
Number of Suspension Towers:	0

Conductor & Accessory Type	3M Stock #	Installation Quantity	Spare Quantity	Total Quantity	Unit	3M Price per Unit to Customer (USD)	3M Extended Price to Customer (USD)
<b>Conductor Information:</b>							
3M ACCR 270-T35 Conductor	80-6114-7597-3	22484	3212	25696	LNFT	\$ [REDACTED]	\$ [REDACTED]
<b>Accessories:</b>							
Dead End Assembly, Single Tongue (W/Terminal)	80-6114-7604-7	42	7	49	Each	\$ [REDACTED]	\$ [REDACTED]
Jumper Terminal (15 Degree)	80-6114-7600-5	14	7	21	Each	\$ [REDACTED]	\$ [REDACTED]
Die (Aluminum)	80-6114-6286-4	2	1	3	Each	\$ [REDACTED]	\$ [REDACTED]
Die (Steel)	80-6114-6297-1	2	1	3	Each	\$ [REDACTED]	\$ [REDACTED]
Soap For Compression Hardware (Gratis Charge)	26-1100-1674-3	8		8	3 Bar Pk	\$ [REDACTED]	\$ [REDACTED]
Hi-Temp Compound (10 tubes per case)	98-0000-0711-6	8	1	9	Case	\$ [REDACTED]	\$ [REDACTED]
Alnox Electrical Joint Compound (10 tubes per case)	80-6114-4712-1	2		2	Case	\$ [REDACTED]	\$ [REDACTED]
Thermolign Suspension Assembly (Single)	98-0000-0714-0	0	0	0	Each	\$ [REDACTED]	\$ -
TG Grips	80-6114-7719-3	23	9	32	Each	\$ [REDACTED]	\$ [REDACTED]
Thimble Clevis for TG-Grips	80-6112-4359-5	23	9	32	Each	\$ [REDACTED]	\$ [REDACTED]
Line Guard (for Jumper)	80-6109-0460-1	28	9	37	Each	\$ [REDACTED]	\$ [REDACTED]
Thermolign Splice	98-0000-0729-8		3	3	Each	\$ [REDACTED]	\$ [REDACTED]
Repair Rods	98-0000-0763-7		3	3	Each	\$ [REDACTED]	\$ [REDACTED]
Protector Rods for PLP Damper	80-6114-4851-7	84	4	88	Each	\$ [REDACTED]	\$ [REDACTED]
Vibration Damper (on suspension/Protector Rods)	80-6114-4675-0	84	4	88	Each	\$ [REDACTED]	\$ [REDACTED]
Friction Tape (3M packaging = 30 rolls/case)	80-6116-0426-7	30		30	Rolls	\$ [REDACTED]	\$ [REDACTED]
						<b>Sub-Total</b>	\$ [REDACTED]

Refundable Reel Deposit (See "Note 5." above.)	80-9999-0825-6	7	1	8	Each	\$ [REDACTED]	\$ [REDACTED]
Procurement Performance Bond Fee	80-9999-0831-4			1	Each	\$ [REDACTED]	\$ [REDACTED]
Approximate Freight Charge				1	Lot	\$ [REDACTED]	\$ [REDACTED]
						<b>Total without Tax</b>	\$ [REDACTED]

Washington State Sales Tax (WSST) Estimated @ 8.4% on total	\$ [REDACTED]
<b>Grand Total including Washington State Sales Tax (WSST) Estimated @ 8.4%</b>	\$ [REDACTED]